

State Level Environment Impact Assessment Authority, Uttar Pradesh

Uploaded on
www.seiaaup.in

Directorate of Environment, U.P.

Vinnet Khandi-I, Gomti Nagar, Lucknow - 226 010

Phone : 91-522-2300 541, Fax : 91-522-2300 543

E-mail : doeupko@yahoo.com

Website : www.seiaaup.in

To,

Shri Manmeet Singh Batra,
Sr. vice President, Head Architect,
M/s Lotus Greens constructions Pvt. Ltd.,
1204, Sector-A, Pocket A,
Vasant Kunj, New Delhi- 110070.

Ref No. 375.../P3rya/SEAC/3652/2016

Date: 22/03/2017

Sub: Environmental Clearance for Group Housing Project at SC-02, H & I, Sector-150, Noida, M/s Lotus Greens Constructions Pvt. Ltd. Regarding,
Dear Sir,

Please refer to your application/letters 02-04-2016, 04-05-2016 & 26-09-2016 addressed to the Secretary, State Level Expert Appraisal Committee (SEAC) and Director, Directorate of Environment Govt. of UP on the subject as above. A presentation was made by the representative of the project proponent along with their consultant M/s Ind Tech House Consult in the SEAC meeting dated 24/12/2016.

The Project proponent, through documents (submitted to SEAC) and presentation made during meeting, has informed to the SEAC that:-

1. The environmental clearance is sought for Group Housing Project at SC-02/H & I, Sector-150, Noida, M/s Lotus Greens Constructions Pvt. Ltd.
2. Total Plot Area of the project is 72,000 sq. m, whereas, total Built-up Area is 2,21,789.01 sq. m.
3. The project comprises 18 (14+4) number of building blocks along with facility building blocks and adequate parking facilities.

4. Salient feature details of the project:

SN	Description	Details	Unit
GENERAL			
1	Plot Area	72000.00	SQM
2	Proposed Built Up Area	221789.01	SQM
3	Number of Residential & Facility Building Blocks	18 (14+4)	NOS
4	Total no of Saleable DU's	1090	NGS
5	Max Height of Building (Upto Terrace)	95.15	M
6	Max Nbr of Floors (Residential Tower)	B+G/ST+31	NOS
7	Cost of Project	321	CR
8	Expected Population (4905 Residential + 1329 Floating)	6234	PERSONS
AREAS			
9	Permissible Ground Coverage Area (30 %)	21600.0	SQM
10	Proposed Ground Coverage Area (13.66 %)	9832	SQM
11	Total Permissible FAR Area (Resd+Commercial) - 209.95 (5% Extra FAR on Residential component for Green Rating)	151164	SQM
12	Total Proposed FAR (Resd+Commercial) Area - 209.35	150734.83	SQM
13	Basement Area	48762.797	SQM
14	Non FAR areas - Facilities	20287	SQM
15	Stilt Areas	2004.06	SQM
16	Proposed Built Up Area	221789.01	SQM
WATER			
17	Total Water Requirement	598	KLD
18	Fresh water requirement (56.42% of total water req)	337.37	KLD
19	Waste water Generation	381.99	KLD
20	Proposed STP Capacity	460	KLD



21	Treated Water Available for Reuse	305.59	KLD
22	Recycled Water (43.58% of total water requirement)	260.63	KLD
23	Surplus treated water	44.96	KLD

RAIN WATER HARVESTING

24	Rain Water Harvesting Potential	20214.74	CUM
25	No of RWH of Pits Proposed (Roof Top)	4	NOS

PARKING

26	Total Parking Required as / Building Bye Laws	1890	ECS
27	Proposed Total Parking	1985	ECS
28	Proposed Surface Parking	483	ECS
29	Proposed Basement Parking	1502	ECS

GREEN AREAS

30	Required Green Area (43.17 % of Plot Area)	31084	SQM
31	Proposed Green Area (43.89 % of Plot Area)	31605	SQM

WASTE GENERATION

32	Municipal Solid Waste Generation	2.61	TPD
33	Quantity of E-Waste Generation- Kg/Day	17	KG/DAY
34	Quantity of Hazardous waste Generation	7.6	LTS/DAY
35	Quantity of Sludge Generated from STP	137.5	KG/DAY

POWER

36	Total Power Requirement	6540	KVA
37	DG set backup	5540	KVA
38	No of DG Sets	(4X1010+2X750)	KVA

5. Land use details:

S. No.	Particulars	Area in Sqm	Percentage
1	Buildings	9832	13.66
2	Road Area	9660	13.42
3	Surface Parking	5292	7.35
4	Green Area	31605	43.90
5	Other open Areas	15611	21.68
	Total Plot Area	72,000	100

6. Water requirement details:

S. No.	Description	Occupancy Capacity / Area	Rate (Liters)	Total Water Demand (KLD)
A.	Residents			
	Domestic	4905	65	318.83
	Flushing	4905	21	103.01
B.	Non-residential / Working			
	Domestic	190	15	2.85
	Flushing	190	30	5.70
C.	Visitors			
	Domestic	1139	5	5.70
	Flushing	1139	10	11.39
D.	Gardening (within pocket)	31605.3	3.5	110.62
E.	Water Cooled DG Cooling (For 6 Hrs.)	5540	0.9	29.92
F.	Water Body / Swimming Pool	1	0	10
Total Water Requirement				598
Head		Source		Quantity
Fresh Water Requirement		New Okhla Industrial Development Authority		337 KLD
Treated Water Requirement		On site STP		261 KLD

7. Water uses details:

Head	Quantity, KLD
------	---------------



Total Water Requirement	598
Fresh Water Requirement	337
Treated Water Requirement	261
Water for Flushing	120
Gardening	111
DG Cooling	30
Waste Water Generation (80% of total domestic fresh water demand + 100% of Flushing Water)	382
Capacity of STP	460
Treated Water Generation	382
Surplus Treated Water	45

- Estimated Sewage Generation: 382 KLD
- Waste water generated will be treated in on-site STP.
- Proposed treatment methodology : SBR
- Proposed STP (Capacity): 460 KLD
- Treatment up to tertiary level.
- STP shall have power back-up for uninterrupted operation during power failure.
- Treated waste water will be used for horticulture, flushing, and cooling tower.

8. Population details:

POPULATION			
RESIDENTIAL	DU'S	POP/DU	TOTAL
SALEABLE DU'S	1090	4.5	4905
TOTAL			4905
NON RESIDENTIAL			
FACILITIES - CLUB/COMMERCIAL etc (Employees)	AREA		
COMMERCIAL (SHOPPING)	677.95		68
COMMUNITY BLDG	2214.1		22
FACILITY MANAGEMENT STAFF	LS		100
TOTAL			190
VISITORS			
TOTAL NO OF VISITORS			1139
TOTAL POPULATION			6234

9. Parking details:

Particulars	Area (In sq.m)	Number (ECS)	Number (CARS)
Required Parking as per bylaws- RES. (@1ECS/80 and Com @1 ECS/50 SQM FAR Area)	150734.83 (FAR Area)	1890 ECS	
Proposed Parking	-	1985 ECS	1890 CARS (Maximum)
Surface Parking	-	483 ECS	424 CARS
Proposed Parking in Basement	-	1502 ECS	1466 CARS

10. Waste generation details:

Total Waste Generation	2.61	TPD
Organic Waste Generation	1.57	TPD
E- Waste Generation	17	KG/Day
Sludge Generation	141.83	KG/Day
Hazardous Waste Generation (DG Waste Oil)	7.56	Lts/ Day

11. The project proposals are covered under category 8 "b" of EIA Notification, 2006.

12. The project proponent submitted that the structural design of the project has been vetted by Jamia Millia Islamia through letter dated 04/07/2016, Fire NOC has been obtained through letter dated 03/07/2016, Noida Authority has approved the building plans through letter dated 30/09/2016. Organic waste convertor on site for MSW disposal only inert waste shall be taken.. A kachcha pond has been made on

site for harvesting of rain water potential generating apart from rooftop. Total cost of the project is Rs. 311/- Crores.

Based on the recommendations of the State Level Expert Appraisal Committee Meeting (SEAC) held on 26/12/2016 the State Level Environment Impact Assessment Authority (SEIAA) in its Meeting held on 13/02/2017 decided to grant the Environmental Clearance for proposed project along with subject to the effective implementation of the following general and specific conditions:-

General Conditions:

1. It shall be ensured that all standards related to ambient environmental quality and the emission/effluent standards as prescribed by the MoEF are strictly complied with.
2. It shall be ensured that obtain the no objection certificate from the U P pollution control board before start of construction.
3. It shall be ensured that no construction work or preparation of land by the project management except for securing the land is started on the project or the activity without the prior environmental clearance.
4. The proposed land use shall be in accordance to the prescribed land use. A land use certificate issued by the competent Authority shall be obtained in this regards.
5. All trees felling in the project area shall be as permitted by the forest department under the prescribed rules. Suitable clearance in this regard shall be obtained from the competent Authority.
6. Impact of drainage pattern on environment should be provided.
7. Surface hydrology and water regime of the project area within 10 km should be provided.
8. A suitable plan for providing shelter, light and fuel, water and waste disposal for construction labour during the construction phase shall be provided along with the number of proposed workers.
9. Measures shall be undertaken to recycle and reuse treated effluents for horticulture and plantation. A suitable plan for waste water recycling shall be submitted.
10. Obtain proper permission from competent authorities regarding enhanced traffic during and due to construction and operation of project.
11. Obtain necessary clearances from the competent Authority on the abstraction and use of ground water during the construction and operation phases.
12. Hazardous/inflammable/Explosive materials likely to be stored during the construction and operation phases shall be as per standard procedure as prescribed under law. Necessary clearances in this regards shall be obtained.
13. Solid wastes shall be suitably segregated and disposed. A separate and isolated municipal waste collection center should be provided. Necessary plans should be submitted in this regards.
14. Suitable rainwater harvesting systems as per designs of groundwater department shall be installed. Complete proposals in this regard should be submitted.
15. The emissions and effluents etc. from machines, instruments and transport during construction and operation phases should be according to the prescribed standards. Necessary plans in this regard shall be submitted.
16. Water sprinklers and other dust control measures should be undertaken to take care of dust generated during the construction and operation phases. Necessary plans in this regard shall be submitted.
17. Suitable noise abatement measures shall be adopted during the construction and operation phases in order to ensure that the noise emissions do not violate the prescribed ambient noise standards. Necessary plans in this regard shall be submitted.
18. Separate stock piles shall be maintained for excavated top soil and the top soil should be utilized for preparation of green belt.
19. Sewage effluents shall be kept separate from rain water collection and storage system and separately disposed. Other effluents should not be allowed to mix with domestic effluents.
20. Hazardous/Solid wastes generated during construction and operation phases should be disposed off as prescribed under law. Necessary clearances in this regard shall be obtained.
21. Alternate technologies for solid waste disposals (like vermin-culture etc.) should be used in consultation with expert organizations.
22. No wetland should be infringed during construction and operation phases. Any wetland coming in the project area should be suitably rejuvenated and conserved.
23. Pavements shall be so constructed as to allow infiltration of surface run-off of rain water. Fully impermeable pavements shall not be constructed. Construction of pavements around trees shall be as

- per scientifically accepted principles in order to provide suitable watering, aeration and nutrition to the tree.
24. The Green building Concept suggested by Indian Green Building Council, which is a part of CII-Godrej GBC, shall be studied and followed as far as possible.
 25. Compliance with the safety procedures, norms and guidelines as outlined in National Building Code 2005 shall be compulsorily ensured.
 26. Ensure usage of dual flush systems for flush cisterns and explore options to use sensor based fixtures, waterless urinals and other water saving techniques.
 27. Explore options for use of dual pipe plumbing for use of water with different qualities such as municipal supply, recycled water, ground water etc.
 28. Ensure use of measures for reducing water demand for landscaping and using xeriscaping, efficient irrigation equipments & controlled watering systems.
 29. Make suitable provisions for using solar energy as alternative source of energy. Solar energy application should be incorporated for illumination of common areas, lighting for gardens and street lighting in addition to provision for solar water heating. Present a detailed report showing how much percentage of backup power for institution can be provided through solar energy so that use and polluting effects of DG sets can be minimized.
 30. Make separate provision for segregation, collection, transport and disposal of e-waste.
 31. Educate citizens and other stake-holders by putting up hoardings at different places to create environmental awareness.
 32. Traffic congestion near the entry and exit points from the roads adjoining the proposed project site must be avoided. Parking should be fully internalized and no public space should be utilized.
 33. Prepare and present disaster management plan.
 34. The project proponents shall ensure that no construction activity is undertaken without obtaining pre-environmental clearance.
 35. A report on the energy conservation measures conforming to energy conservation norms finalize by Bureau of Energy efficiency should be prepared incorporating details about building materials and technology, R & U Factors etc.
 36. Fly ash should be used as building material in the construction as per the provision of fly ash notification of September, 1999 and amended as on August, 2003 (The above condition is applicable only if the project lies within 100 km of Thermal Power Station).
 37. The DG sets to be used during construction phase should use low sulphur diesel type and should conform to E.P. rules prescribed for air and noise emission standards.
 38. Alternate technologies to Chlorination (for disinfection of waste water) including methods like Ultra Violet radiation, Ozonation etc. shall be examined and a report submitted with justification for selected technology.
 39. The green belt design along the periphery of the plot shall achieve attenuation factor conforming to the day and night noise standards prescribed for residential land use. The open spaces inside the plot should be suitably landscaped and covered with vegetation of indigenous variety.
 40. The construction of the building and the consequent increased traffic load should be such that the micro climate of the area is not adversely affected.
 41. The building should be designed so as to take sufficient safeguards regarding seismic zone sensitivity.
 42. High rise buildings should obtain clearance from aviation department or concerned authority.
 43. Suitable measures shall be taken to restrain the development of small commercial activities or slums in the vicinity of the complex. All commercial activities should be restricted to special areas earmarked for the purpose.
 44. It is suggested that literacy program for weaker sections of society/women/adults (including domestic help) and under privileged children could be provided in a formal way.
 45. The use of Compact Fluorescent lamps should be encouraged. A management plan for the safe disposal of used/damaged CFLs should be submitted.
 46. It shall be ensured that all Street and park lighting is solar powered. 50% of the same may be provided with dual (solar/electrical) alternatives.
 47. Solar water heater shall be installed to the maximum possible capacity. Plans may be drawn up accordingly and submitted with justification.



48. Treated effluents shall be maximally reused to aim for zero discharge. Where ever not possible, a detailed management plan for disposal should be provided with quantities and quality of waste water.
49. The treated effluents should normally not be discharged into public sewers with terminal treatment facilities as they adversely affect the hydraulic capacity of STP. If unable, necessary permission from authorities should be taken.
50. Construction activities including movements of vehicles should be so managed so that no disturbance is caused to nearby residents.
51. All necessary statutory clearances should be obtained and submitted before start of any construction activity and if this condition is violated the clearance, if and when given, shall be automatically deemed to have been cancelled.
52. Parking areas should be in accordance with the norms of MOEF, Government of India. Plans may be drawn up accordingly and submitted.
53. The location of the STP should be such that it is away from human habitation and does not cause problem of odor. Odorless technology options should be examined and a report submitted.
54. The Environment Management plan should also include the break up costs on various activities and the management issues also so that the residents also participate in the implementation of the environment management plan.
55. Detailed plans for safe disposal of STP sludge shall be provided along with ultimate disposal location, quantitative estimates and measures proposed.
56. Status of the project as on date shall be submitted along with photographs from North, South, West and East side facing camera and adjoining areas should be provided.
57. Specific location along with dimensions with reference to STP, Parking, Open areas and Green belt etc should be provided on the layout plan.
58. The DG sets shall be so installed so as to conform to prescribed stack heights and regulations and also to the noise standards as prescribed. Details should be submitted.
59. E-Waste Management should be done as per MoEF guidelines.
60. Electrical waste should be segregated & disposed suitably as not to impose Environmental Risk.
61. The use of suitably processed plastic waste in the construction of roads should be considered.
62. Displaced persons shall be suitably rehabilitated as per prescribed norms.
63. Dispensary for first aid shall be provided.
64. Safe disposal arrangement of used toiletries items in Hotels should be ensured. Toiletries items could be given complementary to guests, adopting suitable measures.
65. Diesel generating set stacks should be monitored for CO and HC.
66. Ground Water downstream of Rain Water Harvesting pit nearest to STP should be monitored for bacterial contamination. Necessary Hand Pumps should be provided for sampling. The monitoring is to be done both in pre and post monsoon, seasons.
67. The green belt shall consist of 50% trees, 25% shrubs and 25% grass as per MoEF norms.
68. A Separate electric meter shall be provided to monitor consumption of energy for the operation of sewage/effluent treatment in tanks.
69. An energy audit should be annually carried out during the operational phase and submitted to the authority.
70. Project proponents shall endeavor to obtain ISO: 14001 certification. All general and specific conditions mentioned under this environmental clearance should be included in the environmental manual to be prepared for the certification purposes and compliance.
71. Environmental Corporate Responsibility (ECR) plan along with budgetary provision amounting to 2% of total project cost shall be submitted (within the month) on need base assessment study in the study area. Income generating measures which can help in up-liftment of weaker section of society consistent with the traditional skills of the people identified. The program may include activities such as old age homes, rain water harvesting provisions in nearby areas, development of fodder farm, fruit bearing orchards, vocational training etc. In addition, vocational training for individuals shall be imparted so that poor section of society can take up self employment and jobs. Separate budget for community development activities and income generating programmes shall be specified. Revised ECR plan is to be submitted within 3 month. Failing which, the environmental clearance shall be deemed to be cancelled.
72. Appropriate safety measures should be made for accidental fire.
73. Smoke meters should be installed as warning measures for accidental fires.

74. Plan for safe disposal of R.O reject is to be submitted.

SPECIFIC CONDITIONS:

1. Provision of parking should be restricted to ECS as required under Development Authority bye-laws.
2. Provision of setback on all sides should be made as per Development Authority bye-laws.
3. Copy of all NOCs from different Departments shall be obtained prior to start of construction.
4. Necessary planning for any anticipated expansion should be incorporated in present design in view of structural stability.
5. An underground water reservoir shall be planned within the premises for storage of rain water.
6. Municipal solid waste shall be disposed/managed as per Municipal Solid Waste (Management and Handling) Rules, 2000 (as amended).
7. 15% area of the total plot area shall be compulsorily made available for the green belt development including the peripheral green belt.
8. Project falling within norm area of Wild Life Sanctuary is to obtain a clearance from National Board Wild Life (NBWL) even if the eco-sensitive zone is not earmarked.
9. Criteria/ norms provided by competent Authority regarding the seismic zone be followed for construction work. Provision of alarm system, to timely notify the residents, in case of occurrence of earthquake/other natural disasters/fire should be provided. A well defined evacuation plan should also be prepared and regular mock drills should be arranged for the residents. Rise of stairs should be constructed in a way, so that it should provide smooth movement.
10. For the treatment for total sewage, a full-fledged STP is to be provided with 20% more capacity than waste water generated during operation phase. 100% waste water is to be treated in captive STP conforming to prescribed standards of receiving body for designated use. Monitoring of STP to be done daily till its stabilization.
11. Dual plumbing should be adopted. Recycling of water as proposed shall be undertaken with regular testing and monitoring of treated water.
12. Dedicated power supply for STPs is to be ensured during operation. Sludge of STP is to be used in-house as manure and surplus manure should be managed by giving it to end users. STP shall be suitably located nearest to back side boundary with shortest out let. Operation and the maintenance cost of the STP shall also be informed along with the compliance of the E-waste and municipal solid waste disposal.
13. Total cost of the project is Rs. 311 Crore. Corporate Social Responsibility (CSR) plan along with budgetary provision amounting to 2% of the total project cost (Rs. 6.22 Cr.) shall be prepared and approved by Board of Directors of the company. A copy of resolution as above shall be submitted to the authority. A list of beneficiaries with their mobile nos./address should be submitted alongwith six monthly compliance reports.
14. LEDs should be used in all common areas and corridors. 100% solar lighting is to be provided in the open areas/ stairs cases.
15. All entry/exit point should be bell mouth shaped.
16. To discharge excess treated waste water into public drainage system, permission from the competent authority to be taken prior to any discharge.
17. 100 % provision of Rain Water Harvesting is to be made. RWH shall be initially done only from the roof top. RWH from green and other open areas shall be done only after permission from CGWB.
18. Height of the stack should be provided based on combined DG sets capacity and be 6 mt higher than the tallest building. Necessary permission should be sought prior to operation of DG sets.
19. Post project monitoring for air, water (surface + ground). Stack noise of D.G. sets, STP to be carried out as CPCB Guidelines.
20. Crèche to be provided during the construction/operation phase.
21. LIG & EWS housing to be provided as per U.P. Govt. Orders and building bye laws.
22. Provision of separate room for senior citizen with proper amenities shall be made.
23. Protection shall be provided on the windows of the high rise flats for security of residents.
24. Unless and until all the environmental issues are sorted out the occupancy will be restricted and would be only allowed after achieving the Permission from the competent authority.
25. The project proponent shall ensure that the project site does not attract/infringe any buffer zone of no activity identified/declared under law.
26. For any extraction of ground water, prior permission from CGWB shall be taken.

27. Sprinkler to be used for curing and quenching and ready mix concrete may be used for construction.
28. Possibilities of use of treated waste water for irrigation purposes should be explored. Drip irrigation should be tried upto extent possible. No fresh water will be used for irrigation purpose.
29. Mobile toilets, safe drinking water facility, sanitation facility and eco friendly fuels etc. Shall be made available to the temporary residents/workers at the project site including the proper treatment and the disposal of the wastes.

No construction/operation is to be started without obtaining Prior Environmental Clearance. Concealing factual data and information or submission of false/fabricated data and failure to comply with any of the conditions stipulated in the Prior Environmental Clearance attract action under the provision of Environmental (Protection) Act, 1986.

This Environmental Clearance is subject to ownership of the site by the project proponents in confirmation with approved Master Plan for G.B. Nagar. In case of violation, it would not be effective and would automatically be stand cancelled.

You are also directed to ensure that the proposed site is not a part of any no-development zone as required/prescribed/identified under law. In case of violation, this permission shall automatically deem to be cancelled. Also, in the event of any dispute on ownership or land use of the proposed site, this clearance shall automatically deemed to be cancelled.

The project proponent will have to submit approved plans and proposals incorporating the conditions specified in the Environmental Clearance within 03 months of issue of the clearance. The SEIAA/MoEF reserves the right to revoke the environmental clearance, if conditions stipulated are not implemented to the satisfaction of SEIAA/MoEF. SEIAA may impose additional environmental conditions or modify the existing ones, if necessary. Necessary statutory clearances should be obtained and submitted before start of any construction activity.

These stipulations would be enforced among others under the provisions of Water (Prevention and Control of Pollution) Act, 1974, the Air (Prevention and Control of Pollution) Act, 1981, the Environment (Protection) Act, 1986, the Public Liability (Insurance) Act, 1991 and EIA Notification, 2006 including the amendments and rules made thereafter.

This is to request you to take further necessary action in the matter as per provision of Gazette Notification No. S.O. 1533(E) dated 14.9.2006, as amended and send regular compliance reports to the authority as prescribed in the aforesaid notification.



No. /Paryar/SEAC/3652/2016

Dated: As above

Copy with enclosure for information and necessary action to:

1. The Principal Secretary, Department of Environment, Govt. of Uttar Pradesh, Lucknow.
2. Advisor, IA Division, Ministry of Environment, Forests & Climate Change, Govt. of India, Indira Paryavaran Bhawan, Jor Bagh Road, Aliganj, New Delhi.
3. Chief Conservator, Regional Office, Ministry of Environment & Forests, (Central Region), Kendriya Bhawan, 5th Floor, Sector-H, Aliganj, Lucknow.
4. District Magistrate, G.B. Nagar.
5. The Member Secretary, U.P. Pollution Control Board, TC-12V, Paryavaran Bhawan, Vibhuti Khand, Gomti Nagar, Lucknow.
6. Regional Officers, Regional Office, UP Pollution Control Board, Noida.
7. Copy to Web Master/ guard file.

(Shruti Shukla)
Deputy Director,
Directorate of Environment, U.P.

	<p><i>asked the project proponent to submit and upload the revised Form-1 and 1-A.</i></p> <p><i>The proposal was deferred till the desired information is submitted.</i></p>
21.5.12	<p>Residential Apartment " Mantri Hennur" at K.R Puram Hobli, Bangalore East, Bangalore by M/s. Mantri Developers Pvt Ltd - Environmental Clearance (IA/KA/NCP/64941/2015; F.No. 21-218/2017-IA-III)</p> <p><i>The Committee was informed that the Project Proponent has made a request that due to non-receipt of Certified Compliance report from RO, MoEF&CC. Accordingly, he is not able to attend the meeting.</i></p> <p><i>The proposal was, therefore, deferred till the desired information is submitted.</i></p>
21.5.13	<p>Group Housing Project at SC-02/ H&I, Sector 150, Noida by M/s Brick Rise Developers Pvt Ltd - Amendment in Environmental Clearance (IA/UP/MIS/66817/2017; F. No. 21-249/2017-IA-III)</p> <p>The project proponent made a presentation and provided the following information to the Committee:-</p> <ul style="list-style-type: none"> (i) Environment Clearance was received for project from SEIAA Uttar Pradesh vide letter No. 375/Parya/SEAC/3652/2016 dated 22.03.2017 in favour of M/s Lotus Greens Constructions Pvt. Ltd., SC-02/ H&I, Sector 150, Noida, Uttar Pradesh (ii) The said project will be developed by M/s Brick Rise Developers Pvt. Ltd which is wholly own subsidiary company of M/s Lotus Greens Constructions Pvt. Ltd. Copy of certificate from Registrar of Companies is enclosed herewith. (iii) Request to change the name of company in EC Letter from M/s Lotus Greens Constructions Pvt. Ltd. to M/s Brick Rise Developers Pvt. Ltd. <p><i>The Committee deliberated on the Copy of certificate from Registrar of Companies dated 23.03.2016 and allowed the change of name from M/s Lotus Greens Constructions Pvt. Ltd. to M/s Brick Rise Developers Pvt. Ltd. subject to submission of affidavit/undertaking to abide by the conditions prescribed in the environmental clearance issued for the project.</i></p>
21.5.14	<p>Phase II development of Krishnapatnam Port at Krishnapatnam Sh Potti Sriramulu Nellore Distt, A.P. by M/s Krishnapatnam Port - Extension of validity of Environmental and CRZ Clearance (IA/AP/MIS/566/2009; F. No. 11-62/2009-IA.III)</p> <p>The project proponent made a presentation and provided the following information to the Committee:-</p> <ul style="list-style-type: none"> (i) Development of a Deep Water, all weather, multipurpose port at Krishnapatnam SPSR Nellore District, AP is being implemented as a PPP Project on BOST basis by M/s. Krishnapatnam Port Company Limited (KPCL) in terms of the Concession Agreement (CA) entered into with Government of Andhra Pradesh (GoAP). (ii) Phase-I development of the port with 3 berths to handle 28 MTPA of non-container cargo. Phase –I was completed and commissioned in 2009 in terms of Environmental& CRZ Clearance granted vide MoEFOrder No 10-22/2005-IA-III dated 26.07.2006. (iii) Environmental& CRZ Clearance was granted vide MoEF's order F.No.11-62/2009-IA.III dated 13.11.2009 for the Phase-II Development of Krishnapatnam Port with 14 berths to

7TH FLOOR, TOWER -B, PLOT NO. 8, SECTOR - 127, NOIDA - 201301
CIN - U70102UP2016PTC077246

श्री. राज. प्रमुख द्वारा प्राप्त किया
 दिनांक 05.09.2017
 प्रमुख, जलवायु परिवर्तन मंत्रालय
 Ministry of Environment, Forests & Climate Change
 Govt. of India
 प्रधान मंत्री भवन/Indira Park, New Delhi
 नई दिल्ली/ New Delhi-110003
 06/09/17


 Black Rose Detective Agency
 1000 14th St. NW
 Seattle, WA 98107
 (206) 461-1111
 www.blackrosecrime.com

Encl. **Copy of Affidavit**



उत्तर प्रदेश UTTAR PRADESH

CZ 083843

AFFIDAVIT

I, Tapan Sangal, S/o Sh. Sudhir Mohan Sangal, residing at E-118, Sector 21, Noida, Uttar Pradesh do hereby solemnly affirm and declare as follows -

1. That, I am the Authorised Signatory of M/s Brick Rise Developers Pvt. Ltd. having its Registered office at 7th floor, Tower B, Plot No. 8, Sector 127, Noida- 201301
2. That, I have been duly authorized by the said Company to affirm this Affidavit and thus competent to do so.
3. That there is no construction carried out at project site as on date.
4. That, there is no litigation on the project either at NGT or any other court of Law.
5. That, The land has been allotted by NOIDA. The land is in our possession and there is no R&R issue.
6. M/s Brick Rise Developers Pvt. Ltd. takes all the liability with its implications & will comply with all the conditions of the Environment Clearance as per the EC letter no. 375/Parya/SEAC/3652/2016 dated 22.3.2017 issued to M/S Lotus Greens

For Brick Rise Developers Private Limited
 Director/Authorised Signatory
 Tapan Sangal
 (Sd/-)
 Govt. of Noida
 11/11/2017

क्रम-संख्या... 11/ स्टाम्प विक्रेता की तिथि...

स्टाम्प कल करने का प्रकार...

स्टाम्प क्रेता का नाम व पुरा पता...

स्टाम्प की अवधि...

विनोद कुमार स्टाम्प विक्रेता

ला. नं. - 146 अथर्व 31-03-20

अथर्व विक्रेता का नाम, पता, मो. नं. व. नं.

विनोद कुमार

02-06-16

Bruck Rise Developers (P) Ltd

Sect - 127 NOIDA

Constructions Pvt. Ltd. for Group Housing Project at SC-02, H&I, Sector 150
Noida.

For Brick Rise Developers Private Limited

DEPONENT
Director

Verification:

Verified at Noida on this day of 23rd August, 2017 that the contents of foregoing paragraphs of this Affidavit are true to the best of my knowledge and belief and nothing has been concealed therein.

For Brick Rise Developers Private Limited

DEPONENT
Director/Authorized Signatory

ATTESTED

MAHAVIR SINGH
NOTARY
G. B. NABAR

23 AUG 2017

